

2020 Crack Filling/Seal Coating/Striping at Multiple Locations

| | Maul Enterprises Inc. | Chicagoland Paving Contractors Inc. | Hastings Asphalt Services Inc. | Patriot Maintenance Inc. | SKC Construction Inc. | Pavement Systems Inc. | Everest Paving |
|--|-----------------------|-------------------------------------|--------------------------------|--------------------------|-----------------------|-----------------------|----------------|
| BID BOND | X | X | X | Cashier's Check | X | X | X |
| <i>CANNON CROSSING PARKING LOT</i> | | | | | | | |
| Item #1: Rout and clean any crack greater than ¼" in width and filled with a single component hot tar joint sealant meeting IDOT specifications. (7,980 lineal feet) | \$0.55 | \$0.65 | \$0.73 | \$0.38 | \$0.43 | \$0.45 | \$0.87 |
| | \$4,389.00 | \$5,187.00 | \$5,825.40 | \$3,032.00 | \$3,431.40 | \$3,591.00 | \$6,950.00 |
| <i>FREEDOM RUN DOG PARK PARKING LOT</i> | | | | | | | |
| Item #1: Rout and clean any crack greater than ¼" in width and filled with a single component hot tar joint sealant meeting IDOT specifications. (1,540 lineal feet) | \$0.55 | \$0.65 | \$0.73 | \$0.38 | \$0.43 | \$0.45 | \$1.85 |
| | \$847.00 | \$1,001.00 | \$1,124.00 | \$586.00 | \$662.20 | \$693.00 | \$2,850.00 |
| <i>BRIDGES OF POPLAR CREEK COUNTRY CLUB MAINTENANCE DRIVE</i> | | | | | | | |
| Item #1: Rout and clean any crack greater than ¼" in width and filled with a single component hot tar joint sealant meeting IDOT specifications. (4,000 lineal feet) | \$0.55 | \$0.65 | \$0.73 | \$0.38 | \$0.43 | \$0.45 | \$0.74 |
| | \$2,200.00 | \$2,600.00 | \$2,920.00 | \$1,520.00 | \$1,720.00 | \$1,800.00 | \$2,950.00 |
| ALTERNATE #1: Supply and place 2" compacted surface asphalt to designated area prepped by owner, (800 square feet). | \$4.00 | \$4.40 | \$3.75 | \$4.00 | \$6.18 | \$6.66 | \$9.50 |
| | \$3,200.00 | \$3,520.00 | \$3,000.00 | \$3,200.00 | \$4,944.00 | \$5,325.00 | \$7,600.00 |
| <i>BRIDGES OF POPLAR CREEK COUNTRY CLUB PARKING LOT</i> | | | | | | | |
| Item #1: Rout and clean any crack greater than ¼" in width and filled with a single component hot tar joint sealant meeting IDOT specifications. (17,556 lineal feet) | \$0.55 | \$0.50 | \$0.73 | \$0.38 | \$0.43 | \$0.45 | \$0.51 |
| | \$9,655.80 | \$8,778.00 | \$12,815.88 | \$6,672.00 | \$7,549.00 | \$7,900.00 | \$8,900.00 |
| Item #2: Clean entire parking lot including adjacent B6-12 curb gutters, remove all debris from site. Chemically treat all oil stained areas. | \$500.00 | \$550.00 | \$500.00 | Included | \$950.00 | \$2,400.00 | \$114.00 |
| Item #3: Apply 2 coats TARCONITE or approved equal emulsion that exceeds IDOT specifications RP- 355E with 3-5 lbs per gallon of silica sand with an application coverage rate of no less than .3 gallons per square yard or 3.3 square yards per gallon. | \$0.090 | \$0.110 | \$0.095 | \$0.073 | \$0.100 | \$0.056 | \$0.130 |
| | \$15,795.00 | \$19,305.00 | \$16,672.50 | \$12,812.00 | \$17,550.00 | \$9,766.00 | \$23,050.00 |
| Item #4: Pavement markings: Stalls (324, white) | \$3.00 | \$6.60 | \$3.00 | \$1.50 | \$6.00 | \$3.00 | \$9.77 |
| | \$972.00 | \$2,138.40 | \$972.00 | \$486.00 | \$1,944.00 | \$972.00 | \$3,167.00 |
| Item #5: Pavement markings: Handicap Spaces (9 handicapped, Symbols on blue, yellow with hatch van space) | \$69.00 | \$45.00 | \$32.00 | \$15.00 | \$32.50 | \$75.00 | \$46.00 |
| | \$621.00 | \$405.00 | \$288.00 | \$135.00 | \$292.50 | \$675.00 | \$414.00 |
| Item #6: Pavement markings: Arrows (2 arrows, white) | \$25.00 | \$35.00 | \$20.00 | \$15.00 | \$22.50 | \$30.00 | \$50.00 |
| | \$50.00 | \$70.00 | \$40.00 | \$30.00 | \$45.00 | \$60.00 | \$100.00 |
| Item #7: Pavement markings: Linear Stripes (30 lineal feet, Crosswalk w/ 12" perpendicular stripes, white) | \$2.00 | \$3.00 | \$2.50 | \$2.00 | \$2.00 | \$2.73 | \$0.17 |
| | \$60.00 | \$90.00 | \$75.00 | \$60.00 | \$60.00 | \$82.00 | \$155.00 |
| BRIDGES OF POPLAR CREEK PARKING LOT TOTAL PROJECT COSTS | \$27,653.80 | \$31,336.40 | \$31,363.38 | \$20,195.00 | \$28,390.58 | \$21,855.00 | \$35,900.00 |
| TOTAL COST OF ALL FOUR PROJECTS | \$35,089.80 | \$40,124.40 | \$40,732.98 | \$28,533.00* | \$39,148.18* | \$33,264.00* | \$48,650.00 |

* : Alternate was included in TOTAL COST